



**ADDENDUM NO. 1**

TO: All Contractors Bidding

FROM: Christopher J. Stritzel, P.E.  
Crawford, Murphy & Tilly, Inc.

RE: Legacy Pointe Town Center  
First Addition – Bid Package No. 1  
Springfield, IL

DATE: February 10, 2010

**This addendum is an integral part of the contract documents and shall be treated as such.**

**ADDENDUM #1**

Please find attached a summary of total earthwork quantities for the MEC – Sanitary, Storm and Roadway Embankment Plans and the Shive-Hattery Storm Water Management Package. These quantities are being provided for information only to assist the Contractor during the bidding process. The quantities shown were calculated utilizing different surfaces generated from computer models of the existing and proposed improvements. The Contractor shall be required to verify the accuracy of shown quantities during the bidding process.

**END OF ADDENDUM #1**

**Legacy Pointe Town Center**  
 Bid Package No. 1 - Earthwork Calcs

**ADDENDUM NO. 1**

**CLAY SOIL SUMMARY**

<b>Excavation</b>		
West Ditch	28,799	
South Ditch	45,282	
Northwest Ditch	448	
Legacy Pointe Drive	578	
Utility Excavations - MEC Plans	3,500	
<del>Utility Excavations - SH Plans</del>	-	
Sallenger Stockpile	3,000	
Caisson/Footing Dirt	3,000	
<b>Total Clay Available</b>		<b>84,607 CY</b>
<b>Placement (23% Shrinkage)</b>		
Lincolnshire Blvd.	34,944	
Legacy Blvd.	1,231	
North Grading Area	26,147	
South Grading Area	22,133	
<b>Total Clay Placement</b>		<b>84,455</b>
<b>Balance</b>		<b>152 CY</b>

**TOPSOIL SUMMARY**

<b>Stripping</b>		
West Ditch - 6"	2,814	
South Ditch - 6"	3,853	
Northwest Ditch - 6"	63	
Lincolnshire Blvd. - 6"	6,035	
Legacy Pointe Dr. - 6"	1,245	
North Grading Area - 8"	11,262	
South Grading Area - 8"	6,766	
<b>Total Topsoil Available</b>		<b>32,038 CY</b>
<b>Placement (15% Shrinkage)</b>		
West Ditch - Varies	7,298	
South Ditch - Varies	13,567	
Northwest Ditch - 3"	75	
Lincolnshire Blvd. - 3"	1,780	
Legacy Blvd. - 3"	-	
North Grading Area - 3"	4,854	
South Grading Area - 3"	2,918	
<b>Total Topsoil Placement</b>		<b>30,492</b>
<b>Balance</b>		<b>1,546 CY</b>

**EAST OF MACARTHUR SUMMARY**

<b>Excavation</b>		
SE Pond 1	5,345	
<b>Topsoil Stripping</b>		
SE Pond 1 - 6"	489	
<b>Topsoil Placement</b>		
SE Pond 1 - 3"	244	
Clay Stockpile -3"	244	